

BID ITEM LIST

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0001	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
0002	090105	TIME-RELATED OVERHEAD (LS)	LS	LUMP SUM
0003	090205	DISPUTE RESOLUTION BOARD ON-SITE MEETING	EA	4
0004	090210	HOURLY OFF-SITE DISPUTE-RESOLUTION-BOARD-RELATED TASKS	HR	20
0005	100100	DEVELOP WATER SUPPLY	LS	LUMP SUM
0006	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
0007	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
0008	010413	PORTABLE RADAR SPEED FEEDBACK SIGN SYSTEMS (LS)	LS	LUMP SUM
0009	128651	PORTABLE CHANGEABLE MESSAGE SIGN (EA)	EA	4
0010	128659	END OF QUEUE MONITORING AND WARNING WITH TRUCK MOUNTED CHANGEABLE MESSAGE SIGN	DAY	20
0011	129000	TEMPORARY RAILING (TYPE K)	LF	240
0012	014105	ALTERNATIVE TEMPORARY CRASH CUSHION TL-3	EA	1
0013	013357	AUTOMATED FLAGGER ASSISTANCE DEVICE	LS	LUMP SUM
0014	130100	JOB SITE MANAGEMENT	LS	LUMP SUM
0015	130201	WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM
0016	130505	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	EA	2
0017	130520	TEMPORARY HYDRAULIC MULCH	SQYD	4,000
0018	130610	TEMPORARY CHECK DAM	LF	80
0019	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	6
0020	130640	TEMPORARY FIBER ROLL	LF	1,000

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0021	130730	STREET SWEEPING	LS	LUMP SUM
0022	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM
0023	141120	TREATED WOOD WASTE	LB	60
0024	146002	CONTRACTOR-SUPPLIED BIOLOGIST (LS)	LS	LUMP SUM
0025	190101	ROADWAY EXCAVATION	CY	1,920
0026	017963	ROADWAY EXCAVATION (BOULDER REMOVAL)	CY	6,940
0027	190161	ROCK EXCAVATION	CY	1,810
0028	390132	HOT MIX ASPHALT (TYPE A)	TON	1,120
0029	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	50
0030	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	50
0031	397005	TACK COAT	TON	4
0032	398200	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	14,300
0033	510094	(F) - STRUCTURAL CONCRETE, DRAINAGE INLET	CY	11
0034	510502	(F) - MINOR CONCRETE (MINOR STRUCTURE)	CY	0.5
0035	665025	24" CORRUGATED STEEL PIPE (.138" THICK)	LF	300
0036	710132	REMOVE CULVERT (LF)	LF	220
0037	710150	REMOVE INLET	EA	4
0038	710152	REMOVE HEADWALL	EA	1
0039	723080	ROCK SLOPE PROTECTION (60 LB, CLASS II, METHOD B) (CY)	CY	27
0040	729011	ROCK SLOPE PROTECTION FABRIC (CLASS 8)	SQYD	80

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0041	750001	(F) - MISCELLANEOUS IRON AND STEEL	LB	2,365
0042	037492	DOUBLE TWISTED WIRE MESH DRAPERY SYSTEM	SQFT	29,700
0043	017976	CABLE NET ATTENUATOR (SQFT)	SQFT	279,000
0044	017977	CABLE NET DRAPERY (SQFT)	SQFT	27,500
0045	017964	REMOVE EXISTING ROCKFALL FENCE	LF	2,330
0046	820112	MARKER (CULVERT)	EA	11
0047	820220	REMOVE MARKER	EA	8
0048	820250	REMOVE ROADSIDE SIGN	EA	1
0049	820760	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	42
0050	820840	ROADSIDE SIGN - ONE POST	EA	1
0051	832018	MIDWEST GUARDRAIL SYSTEM (8' STEEL POST)	LF	300
0052	839588	BURIED POST END ANCHOR (TYPE B-F)	EA	1
0053	839752	REMOVE GUARDRAIL	LF	300
0054	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	9,000
0055	847104	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (RECESSED)	LF	9,000
0056	999990	MOBILIZATION	LS	LUMP SUM