

**BID ITEM LIST**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0001	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
0002	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	145
0003	090140	RENEWABLE DIESEL REPORT	EA	2
0004	090205	DISPUTE RESOLUTION BOARD ON-SITE MEETING	EA	5
0005	090210	HOURLY OFF-SITE DISPUTE-RESOLUTION-BOARD-RELATED TASKS	HR	20
0006	100100	DEVELOP WATER SUPPLY	LS	LUMP SUM
0007	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
0008	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
0009	120103	STATIONARY IMPACT ATTENUATOR VEHICLE	DAY	100
0010	120149	TEMPORARY PAVEMENT MARKING (PAINT)	SQFT	250
0011	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	19,600
0012	120165	CHANNELIZER (SURFACE MOUNTED)	EA	120
0013	120204	PORTABLE RADAR SPEED FEEDBACK SIGN SYSTEM DAY	EA	160
0014	120300	TEMPORARY PAVEMENT MARKER	EA	400
0015	120320	TEMPORARY BARRIER SYSTEM	LF	10,700
0016	124000	TEMPORARY PEDESTRIAN ACCESS ROUTE	LS	LUMP SUM
0017	128651	PORTABLE CHANGEABLE MESSAGE SIGN (EA)	EA	13
0018	014105	ALTERNATIVE TEMPORARY CRASH CUSHION TL-3	EA	16
0019	130100	JOB SITE MANAGEMENT	LS	LUMP SUM
0020	130300	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0021	130310	RAIN EVENT ACTION PLAN	EA	39
0022	130320	STORM WATER SAMPLING AND ANALYSIS DAY	EA	27
0023	130330	STORM WATER ANNUAL REPORT	EA	3
0024	130560	TEMPORARY SOIL BINDER	SQYD	12,000
0025	130570	TEMPORARY COVER	SQYD	1,000
0026	130640	TEMPORARY FIBER ROLL	LF	3,000
0027	130650	TEMPORARY GRAVEL BAG BERM	LF	2,000
0028	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM
0029	141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	4,200
0030	141120	TREATED WOOD WASTE	LB	1,400
0031	146002	CONTRACTOR-SUPPLIED BIOLOGIST (LS)	LS	LUMP SUM
0032	153248	REMOVE CONCRETE (MISCELLANEOUS) (SQFT)	SQFT	15,900
0033	170103	CLEARING AND GRUBBING (LS)	LS	LUMP SUM
0034	180106	DUST PALLIATIVE	LS	LUMP SUM
0035	190101	ROADWAY EXCAVATION	CY	7,110
0036	190185	SHOULDER BACKING	TON	100
0037	198010	IMPORTED BORROW (CY)	CY	670
0038	198209	SUBGRADE ENHANCEMENT GEOTEXTILE, CLASS B2	SQYD	1,700
0039	200114	ROCK BLANKET	SQFT	12,200
0040	206400	CHECK AND TEST EXISTING IRRIGATION FACILITIES	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0041	206402	OPERATE EXISTING IRRIGATION FACILITIES	LS	LUMP SUM
0042	206405	REMOVE IRRIGATION FACILITY	LS	LUMP SUM
0043	206559	CONTROL AND NEUTRAL CONDUCTORS (ARMOR-CLAD)	LS	LUMP SUM
0044	208447	POP-UP SPRINKLER ASSEMBLY (GEAR DRIVEN)	EA	18
0045	208588	3" GATE VALVE	EA	6
0046	208598	(F) - 2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	1,080
0047	208607	(F) - 3" PLASTIC PIPE (CLASS 315) (SUPPLY LINE)	LF	180
0048	208821	12" WELDED STEEL PIPE CONDUIT	LF	80
0049	210300	HYDROMULCH	SQFT	44,100
0050	260203	CLASS 2 AGGREGATE BASE (CY)	CY	1,490
0051	390100	PRIME COAT	TON	16
0052	390132	HOT MIX ASPHALT (TYPE A)	TON	5,690
0053	390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	1,500
0054	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	1,300
0055	394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	280
0056	394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	LF	2,860
0057	394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	2,300
0058	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	85
0059	397005	TACK COAT	TON	7
0060	398001	REMOVE ASPHALT CONCRETE PAVEMENT (SQFT)	SQFT	600

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0061	398100	REMOVE ASPHALT CONCRETE DIKE	LF	5,020
0062	398200	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	8,320
0063	510092	(F) - STRUCTURAL CONCRETE, HEADWALL	CY	6
0064	510094	(F) - STRUCTURAL CONCRETE, DRAINAGE INLET	CY	20
0065	510502	(F) - MINOR CONCRETE (MINOR STRUCTURE)	CY	2
0066	650010	12" REINFORCED CONCRETE PIPE	LF	2
0067	650014	18" REINFORCED CONCRETE PIPE	LF	74
0068	650018	24" REINFORCED CONCRETE PIPE	LF	32
0069	710126	REMOVE OVERSIDE DRAIN	EA	4
0070	710132	REMOVE CULVERT (LF)	LF	24
0071	710150	REMOVE INLET	EA	4
0072	710152	REMOVE HEADWALL	EA	1
0073	730070	DETECTABLE WARNING SURFACE	SQFT	120
0074	731504	MINOR CONCRETE (CURB AND GUTTER)	CY	12
0075	731627	MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	CY	15
0076	731710	REMOVE CONCRETE CURB (LF)	LF	20
0077	731840	REMOVE CONCRETE (CURB AND GUTTER)	LF	2,600
0078	731850	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK) (CY)	CY	12
0079	733000	PRE/POST CONSTRUCTION SURVEYS	EA	4
0080	750001	(F) - MISCELLANEOUS IRON AND STEEL	LB	1,352

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0081	810120	REMOVE PAVEMENT MARKER	EA	270
0082	810170	DELINEATOR (CLASS 1)	EA	56
0083	810190	GUARD RAILING DELINEATOR	EA	110
0084	810230	PAVEMENT MARKER (RETROREFLECTIVE)	EA	370
0085	820112	MARKER (CULVERT)	EA	3
0086	820113	TREATMENT BEST MANAGEMENT PRACTICE MARKER	EA	2
0087	820250	REMOVE ROADSIDE SIGN	EA	10
0088	820760	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	470
0089	820840	ROADSIDE SIGN - ONE POST	EA	10
0090	820860	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	44
0091	832006	MIDWEST GUARDRAIL SYSTEM (STEEL POST)	LF	2,650
0092	832018	MIDWEST GUARDRAIL SYSTEM (8' STEEL POST)	LF	270
0093	832070	VEGETATION CONTROL (MINOR CONCRETE)	SQYD	810
0094	839580	END ANCHOR ASSEMBLY (TYPE SFT-M)	EA	4
0095	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	3
0096	840516	THERMOPLASTIC PAVEMENT MARKING (ENHANCED WET NIGHT VISIBILITY)	SQFT	4,010
0097	846007	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	14,800
0098	846013	12" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	3,580
0099	846020	REMOVE PAINTED TRAFFIC STRIPE	LF	19,600
0100	846025	REMOVE PAINTED PAVEMENT MARKING	SQFT	250

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0101	846030	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	8,450
0102	846035	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	270
0103	870009	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM
0104	870510	RAMP METERING SYSTEM	LS	LUMP SUM
0105	871300	CAMERA SYSTEMS	LS	LUMP SUM
0106	872131	MODIFYING LIGHTING SYSTEMS	LS	LUMP SUM
0107	872133	MODIFYING SIGNAL AND LIGHTING SYSTEMS	LS	LUMP SUM
0108	872134	MODIFYING RAMP METERING SYSTEMS	LS	LUMP SUM
0109	999990	MOBILIZATION	LS	LUMP SUM