

BID ITEM LIST

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0001	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
0002	090105	TIME-RELATED OVERHEAD (LS)	LS	LUMP SUM
0003	090200	DISPUTE RESOLUTION ADVISOR ON-SITE MEETING	EA	5
0004	090207	HOURLY OFF-SITE DISPUTE-RESOLUTION-ADVISOR-RELATED TASKS	HR	10
0005	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
0006	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
0007	120149	TEMPORARY PAVEMENT MARKING (PAINT)	SQFT	24
0008	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	150
0009	120165	CHANNELIZER (SURFACE MOUNTED)	EA	29
0010	120182	PORTABLE DELINEATOR	EA	70
0011	120320	TEMPORARY BARRIER SYSTEM	LF	900
0012	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM
0013	014105	ALTERNATIVE TEMPORARY CRASH CUSHION TL-3	EA	2
0014	013357	AUTOMATED FLAGGER ASSISTANCE DEVICE	LS	LUMP SUM
0015	130100	JOB SITE MANAGEMENT	LS	LUMP SUM
0016	130201	WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM
0017	130505	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	EA	6
0018	130520	TEMPORARY HYDRAULIC MULCH	SQYD	530
0019	130570	TEMPORARY COVER	SQYD	530
0020	130610	TEMPORARY CHECK DAM	LF	75

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0021	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	1
0022	130640	TEMPORARY FIBER ROLL	LF	940
0023	130650	TEMPORARY GRAVEL BAG BERM	LF	200
0024	130680	TEMPORARY SILT FENCE	LF	850
0025	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	2
0026	130730	STREET SWEEPING	LS	LUMP SUM
0027	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM
0028	146002	CONTRACTOR-SUPPLIED BIOLOGIST (LS)	LS	LUMP SUM
0029	146007	INVASIVE SPECIES CONTROL	LS	LUMP SUM
0030	160110	TEMPORARY HIGH-VISIBILITY FENCE	LF	170
0031	170103	CLEARING AND GRUBBING (LS)	LS	LUMP SUM
0032	015653	ROOTWADS (EA)	EA	2
0033	190101	ROADWAY EXCAVATION	CY	5,520
0034	190185	SHOULDER BACKING	TON	78
0035	048523	(F) - STRUCTURE EXCAVATION (SOLDIER PILE WALL, TYPE D)	CY	1,340
0036	193029	(F) - STRUCTURE BACKFILL (SOLDIER PILE WALL)	CY	82
0037	193116	(F) - CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	158
0038	193119	(F) - LEAN CONCRETE BACKFILL	CY	258
0039	037634	HYDRAULIC BIOTIC GROWTH MEDIUM	SQFT	19,100
0040	210255	FIBER REINFORCED MATRIX (SQFT)	SQFT	19,100

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0041	210350	FIBER ROLLS	LF	1,130
0042	210610	COMPOST (CY)	CY	41
0043	260203	CLASS 2 AGGREGATE BASE (CY)	CY	510
0044	390025	SEGMENT CORRECTION	EA	1.5
0045	390132	HOT MIX ASPHALT (TYPE A)	TON	2,890
0046	391006	ASPHALT BINDER (GEOSYNTHETIC PAVEMENT INTERLAYER)	TON	130
0047	393004	GEOSYNTHETIC PAVEMENT INTERLAYER (PAVING FABRIC)	SQYD	170
0048	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	1,890
0049	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	8
0050	397005	TACK COAT	TON	7
0051	398100	REMOVE ASPHALT CONCRETE DIKE	LF	1,910
0052	398200	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	1,540
0053	460210	GROUND ANCHOR (SUBHORIZONTAL)	EA	161
0054	048524	STEEL SOLDIER PILE (W 18 X 55)	LF	2,320
0055	490403	30" DRILLED HOLE	LF	2,125
0056	046647	(F) - STRUCTURAL CONCRETE, WALER	CY	208
0057	510092	(F) - STRUCTURAL CONCRETE, HEADWALL	CY	6.5
0058	046648	(F) - BAR REINFORCING STEEL (WALER)	LB	64,310
0059	575004	(F) - TIMBER LAGGING	MFBM	50
0060	590120	CLEAN AND PAINT STEEL SOLDIER PILING	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0061	665012	12" CORRUGATED STEEL PIPE (.079" THICK)	LF	70
0062	665033	30" CORRUGATED STEEL PIPE (.138" THICK)	LF	150
0063	038881	12" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	275
0064	048525	12" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	LF	10
0065	690110	12" CORRUGATED STEEL PIPE DOWNDRAIN	LF	75
0066	692005	12" ENTRANCE TAPER	EA	2
0067	710118	REMOVE ENTRANCE TAPER	EA	2
0068	710126	REMOVE OVERSIDE DRAIN	EA	2
0069	710132	REMOVE CULVERT (LF)	LF	160
0070	710152	REMOVE HEADWALL	EA	1
0071	710196	ADJUST INLET	EA	1
0072	013729	GRAVEL FILTER	CY	6
0073	723070	ROCK SLOPE PROTECTION (150 LB, CLASS III, METHOD B) (CY)	CY	26
0074	760010	DESTROY WELL	EA	5
0075	810120	REMOVE PAVEMENT MARKER	EA	170
0076	810190	GUARD RAILING DELINEATOR	EA	8
0077	810250	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	150
0078	820112	MARKER (CULVERT)	EA	2
0079	820220	REMOVE MARKER	EA	2
0080	820590	RELOCATE ROADSIDE SIGN-ONE POST	EA	1

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0081	832018	MIDWEST GUARDRAIL SYSTEM (8' STEEL POST)	LF	370
0082	832070	VEGETATION CONTROL (MINOR CONCRETE)	SQYD	220
0083	839521	(F) - CABLE RAILING	LF	294
0084	015299	ALTERNATIVE IN-LINE TERMINAL TL-3	EA	2
0085	840623	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (BROKEN 36-12)	LF	360
0086	846007	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	6,440
0087	846030	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	3,750
0088	846051	12" RUMBLE STRIP (ASPHALT CONCRETE PAVEMENT)	STA	17
0089	872002	TEMPORARY SIGNAL SYSTEMS	LS	LUMP SUM
0090	999990	MOBILIZATION	LS	LUMP SUM