

BID FORM (EXHIBIT A)
MATTOLE ROAD (F3D010) OVER MATTOLE RIVER
BRIDGE No. 04C0263
PROJECT NO.: BRLS-5904(024)
CONTRACT NO.: 594055

Item No.	Item Code	Description (F)	Unit of Measure	Estimated Quantity	Unit Price	Total
1	047323	CALIFORNIA ST-75 BRIDGE RAIL	LF	852		
2	070030	LEAD COMPLIANCE PLAN	LS	1		
3	080060	LEVEL 2 CRITICAL PATH METHOD SCHEDULE	LS	1		
4	090105	TIME-RELATED OVERHEAD	LS	1		
5	120090	CONSTRUCTION AREA SIGNS	LS	1		
6	120100	TRAFFIC CONTROL SYSTEM	LS	1		
7	120120	TYPE III BARRICADE	EA	6		
8	120206	PORTABLE SIGNAL SYSTEMS (EA)	EA	4		
9	129000	TEMPORARY RAILING (TYPE K)	LF	240		
10	129090	TEMPORARY ALTERNATIVE CRASH CUSHION	EA	8		
11	130100	JOB SITE MANAGEMENT	LS	1		
12	130301	STORM WATER POLLUTION PREVENTION PLAN	LS	1		
13	130320	STORM WATER SAMPLING AND ANALYSIS DAY	EA	33		
14	130330	STORM WATER ANNUAL REPORT	EA	3	\$2000	\$6000
15	130500	TEMPORARY EROSION CONTROL BLANKET	SQYD	1,250		
16	130515	TEMPORARY HYDRAULIC BIOTIC GROWTH MEDIUM	SQFT	190,000		
17	130520	TEMPORARY HYDRAULIC MULCH	SQYD	1,250		
18	130530	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQYD	21,100		
19	130550	TEMPORARY HYDROSEED (MIX 1)	SQYD	1,250		
20	130640	TEMPORARY FIBER ROLL	LF	12,600		
21	130680	TEMPORARY SILT FENCE	LF	12,200		
22	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	4		
23	130900	TEMPORARY CONCRETE WASHOUT	LS	1		
24	131103	WATER QUALITY SAMPLING AND ANALYSIS DAY	EA	16		

Item No.	Item Code	Description (F)	Unit of Measure	Estimated Quantity	Unit Price	Total
25	131104	WATER QUALITY MONITORING REPORT	EA	4		
26	131105	WATER QUALITY ANNUAL REPORT	EA	3		
27	131201	TEMPORARY CREEK DIVERSION SYSTEMS	LS	1		
28	141110	WORK AREA MONITORING (BRIDGE)	LS	1		
29	141120	TREATED WOOD WASTE	LB	62,500		
30	146002	CONTRACTOR-SUPPLIED BIOLOGIST	LS	1		
31	146003	NATURAL RESOURCE PROTECTION PLAN	LS	1		
32	146008	BAT AND BIRD EXCLUSION	LS	1		
33	146010	HYDROACOUSTIC MONITORING	LS	1		
34	160120	36" PAINTED LATHE (ORANGE)	LF	12,200		
35	170103	CLEARING AND GRUBBING (LS)	LS	1		
36	173001	REMOVE TREE	EA	46		
37	173002	LOG/ROOT WAD STRUCTURE	EA	2		
38	190101	ROADWAY EXCAVATION	CY	18,400		
39	190106	ROADWAY EXCAVATION (TYPE Z-3) (AERIALY DEPOSITED LEAD)	CY	70		
40	192003	STRUCTURE EXCAVATION (BRIDGE) (F)	CY	239		
41	192037	STRUCTURE EXCAVATION (RETAINING WALL) (F)	CY	196		
42	193003	STRUCTURE BACKFILL (BRIDGE) (F)	CY	139		
43	193013	STRUCTURE BACKFILL (RETAINING WALL) (F)	CY	215		
44	198010	IMPORTED BORROW (CY)	CY	1,390		
45	198215	SUBGRADE ENHANCEMENT GEOGRID	SQYD	7,350		
46	200112	MONUMENT BOULDER	EA	1		
47	204009	PLANT (GROUP I)	EA	140		
48	207100	1 1/2" HDPE DOMESTIC WATER LINE	LF	490		
49	207101	1 1/2" TEMPORARY HDPE DOMESTIC WATER LINE	LF	690		
50	207102	REMOVE 1 1/2" HDPE DOMESTIC WATER LINE	LF	420		
51	210100	BIORETENTION SOIL MEDIA	CY	110		
52	210240	HYDRAULIC BIOTIC GROWTH MEDIUM	SQFT	210,000		

Item No.	Item Code	Description (F)	Unit of Measure	Estimated Quantity	Unit Price	Total
53	210257	FIBER REINFORCED MATRIX	ACRE	5		
54	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	11,000		
55	210280	ROLLED EROSION CONTROL PRODUCT (BLANKET)	SQFT	1,900		
56	210300	HYDROMULCH	SQFT	12,700		
57	210350	FIBER ROLLS	LF	370		
58	210431	HYDROSEED (MIX 1)	SQFT	12,700		
59	210432	HYDROSEED (MIX 2)	SQFT	1,900		
60	260203	CLASS 2 AGGREGATE BASE (CY)	CY	690		
61	260204	TEMPORARY AGGREGATE BASE	CY	450		
62	260401	GRAVEL BASE	CY	970		
63	260402	FISH ROCK	CY	3,650		
64	390132	HOT MIX ASPHALT (TYPE A)	TON	620		
65	390133	TEMPORARY HOT MIX ASPHALT	TON	450		
66	480600	TEMPORARY SHORING	LS	1		
67	480602	TEMPORARY STRUCTURE	LS	1		
68	490609	60" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	304		
69	490616	84" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	206		
70	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING (F)	CY	91		
71	510053	STRUCTURAL CONCRETE, BRIDGE (F)	CY	257		
72	510054	STRUCTURAL CONCRETE, BRIDGE (POLYMER FIBER) (F)	CY	323		
73	510060	STRUCTURAL CONCRETE, RETAINING WALL (F)	CY	51		
74	510502	MINOR CONCRETE (MINOR STRUCTURE) (F)	CY	4		
75	519100	JOINT SEAL (MR 2")	LF	62		
76	520102	BAR REINFORCING STEEL (BRIDGE) (F)	LB	291,542		
77	520103	BAR REINFORCING STEEL (RETAINING WALL) (F)	LB	6,403		
78	550203	FURNISH STRUCTURAL STEEL (BRIDGE) (F)	LB	605,606		
79	550204	ERECT STRUCTURAL STEEL (BRIDGE) (F)	LB	605,606		
80	600097	BRIDGE REMOVAL	LS	1		

Item No.	Item Code	Description (F)	Unit of Measure	Estimated Quantity	Unit Price	Total
81	610404	24" TEMPORARY CULVERT	LF	130		
82	610406	36" TEMPORARY CULVERT	LF	110		
83	641107	18" PLASTIC PIPE	LF	25		
84	682022	CLASS 1 PERMEABLE MATERIAL (BLANKET) (F)	CY	70		
85	703450	WELDED STEEL PIPE CASING (BRIDGE)	LF	370		
86	723050	ROCK SLOPE PROTECTION (1/4 T, CLASS V, METHOD B) (CY)	CY	220		
87	729011	ROCK SLOPE PROTECTION FABRIC (CLASS 8)	SQYD	190		
88	750001	MISCELLANEOUS IRON AND STEEL (F)	LB	239		
89	750501	MISCELLANEOUS METAL (BRIDGE) (F)	LB	15,435		
90	780446	STAIN GALVANIZED SURFACES	LS	1		
91	803100	RECONSTRUCT FENCE	LF	30		
92	820134	OBJECT MARKER (TYPE P)	EA	4		
93	820153	REMOVE OBJECT MARKER	EA	4		
94	820250	REMOVE ROADSIDE SIGN	EA	7		
95	820580	RELOCATE MARKER	EA	1		
96	820610	RELOCATE ROADSIDE SIGN	EA	2		
97	820750	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	15		
98	820840	ROADSIDE SIGN - ONE POST	EA	2		
99	839543	TRANSITION RAILING (TYPE WB-31)	EA	2		
100	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	2		
101	839607	CRASH CUSHION (QUADGUARD M10, TL-2)	EA	2		
102	840501	THERMOPLASTIC TRAFFIC STRIPE	LF	3,120		
103	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	160		
104	999990	MOBILIZATION	LS	1		
Total Bid:						

(F) Denotes Final Pay Item