

BID ITEM LIST

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0001	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
0002	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	60
0003	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
0004	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
0005	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	500
0006	120165	CHANNELIZER (SURFACE MOUNTED)	EA	8
0007	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM
0008	013357	AUTOMATED FLAGGER ASSISTANCE DEVICE	LS	LUMP SUM
0009	130100	JOB SITE MANAGEMENT	LS	LUMP SUM
0010	130201	WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM
0011	130510	TEMPORARY MULCH	SQYD	250
0012	130640	TEMPORARY FIBER ROLL	LF	600
0013	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	1
0014	130730	STREET SWEEPING	LS	LUMP SUM
0015	141120	TREATED WOOD WASTE	LB	50
0016	146002	CONTRACTOR-SUPPLIED BIOLOGIST (LS)	LS	LUMP SUM
0017	170103	CLEARING AND GRUBBING (LS)	LS	LUMP SUM
0018	190101	ROADWAY EXCAVATION	CY	860
0019	210252	BONDED FIBER MATRIX (SQFT)	SQFT	8,000
0020	210350	FIBER ROLLS	LF	400

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0021	260203	CLASS 2 AGGREGATE BASE (CY)	CY	380
0022	390132	HOT MIX ASPHALT (TYPE A)	TON	970
0023	391006	ASPHALT BINDER (GEOSYNTHETIC PAVEMENT INTERLAYER)	TON	0.1
0024	393004	GEOSYNTHETIC PAVEMENT INTERLAYER (PAVING FABRIC)	SQYD	50
0025	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	200
0026	397005	TACK COAT	TON	0.5
0027	398200	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	430
0028	810120	REMOVE PAVEMENT MARKER	EA	68
0029	810130	REMOVE DELINEATOR	EA	7
0030	810250	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	68
0031	820134	OBJECT MARKER (TYPE P)	EA	2
0032	820220	REMOVE MARKER	EA	2
0033	820250	REMOVE ROADSIDE SIGN	EA	7
0034	820750	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	57
0035	820840	ROADSIDE SIGN - ONE POST	EA	5
0036	846007	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	3,260
0037	846013	12" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	120
0038	846030	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	650
0039	846035	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	290
0040	846051	12" RUMBLE STRIP (ASPHALT CONCRETE PAVEMENT)	STA	8

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0041	999990	MOBILIZATION	LS	LUMP SUM