

BID ITEM LIST

PASO ROBLES CREEK BRIDGE AT JACK CREEK ROAD

JACK CREEK ROAD

300556

BASE BID

ITEM NO.	CODE NO.	DESCRIPTION OF ITEM	F = Final Pay Item	APPROX. QUANTITY	UNIT OF MEASURE	UNIT PRICE (IN FIGURES) DOLLARS. CENTS	TOTAL AMOUNT DOLLARS. CENTS
1	66999	CONSTRUCTION STAKING		1	LS	LUMP SUM	
2	70030	LEAD COMPLIANCE PLAN		1	LS	LUMP SUM	
3	120090	CONSTRUCTION AREA SIGNS		1	LS	LUMP SUM	
4	120100	TRAFFIC CONTROL SYSTEM		1	LS	LUMP SUM	
5	120120	TYPE III BARRICADE		5	EA		
6	130000	WATER POLLUTION CONTROL		1	LS	LUMP SUM	
7	130100	JOB SITE MANAGEMENT		1	LS	LUMP SUM	
8	130300	PREPARE STORM WATER POLLUTION PREVENTION PLAN		1	LS	LUMP SUM	
9	130310	RAIN EVENT ACTION PLAN		10	EA		
10	130320	STORM WATER SAMPLING AND ANALYSIS DAY		5	EA		
11	130330	STORM WATER ANNUAL REPORT		2	EA		
12	131103	WATER QUALITY SAMPLING AND ANALYSIS DAY		5	EA		
13	131104	WATER QUALITY MONITORING REPORT		5	EA		

Name of Bidder_____

14	131105	WATER QUALITY ANNUAL REPORT		2	EA		
15	131201	TEMPORARY CREEK DIVERSION SYSTEMS		1	LS	LUMP SUM	
16	146002	CONTRACTOR-SUPPLIED BIOLOGIST (LS)		1	LS	LUMP SUM	
17	146006	FUGITIVE DUST CONTROL PLAN		1	LS	LUMP SUM	
18	146007	INVASIVE SPECIES CONTROL		1	LS	LUMP SUM	
19	160110	TEMPORARY HIGH-VISIBILITY FENCE		1,190	LF		
20	170103	CLEARING AND GRUBBING (LS)		1	LS	LUMP SUM	
21	190101	ROADWAY EXCAVATION		440	CY		
22	192003	STRUCTURE EXCAVATION (BRIDGE)	F	148	CY		
23	192020	STRUCTURE EXCAVATION (TYPE D)	F	32	CY		
24	193003	STRUCTURE BACKFILL (BRIDGE)	F	88	CY		
25	198010	IMPORTED BORROW (CY)		1,770	CY		
26	210430	HYDROSEED		21,700	SQFT		
27	260203	CLASS 2 AGGREGATE BASE (CY)		250	CY		
28	390132	HOT MIX ASPHALT (TYPE A)		160	TON		
29	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)		100	LF		
30	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)		52	SQYD		

Name of Bidder _____

31	490580	PERMANENT STEEL CASING		1	EA		
32	490607	48" CAST-IN-DRILLED-HOLE CONCRETE PILING		62	LF		
33	490684	48" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)		76	LF		
34	490687	84" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)		38	LF		
35	500001	PRESTRESSING CAST-IN-PLACE CONCRETE		1	LS	LUMP SUM	
36	510053	STRUCTURAL CONCRETE, BRIDGE	F	340	CY		
37	510054	STRUCTURAL CONCRETE, BRIDGE (POLYMER FIBER)	F	176	CY		
38	519100	JOINT SEAL (MR 2")		56	LF		
39	520102	BAR REINFORCING STEEL (BRIDGE)	F	178,976	LB		
40	600097	BRIDGE REMOVAL		1	LS	LUMP SUM	
41	620001	BIORETENTION		82	CY		
42	650014	18" REINFORCED CONCRETE PIPE		93	LF		
43	703460	24" WELDED STEEL PIPE CASING (BRIDGE)		120	LF		
44	707117	36" PRECAST CONCRETE PIPE INLET		22	LF		
45	723070	ROCK SLOPE PROTECTION (150 lb, Class III, METHOD B) (CY)		620	CY		
46	723095	ROCK SLOPE PROTECTION (20 lb, Class I, METHOD B) (CY)		22	CY		
47	727000	GRAVEL FILTER		150	CY		

Name of Bidder_____

48	750001	MISCELLANEOUS IRON AND STEEL	F	950	LB		
49	780000	BIRD/BAT EXCLUSION AND BAT HABITAT REPLACEMENT		1	LS	LUMP SUM	
50	800051	FENCE (TYPE WM, METAL POST)		150	LF		
51	803020	REMOVE FENCE		130	LF		
52	820134	OBJECT MARKER (TYPE P)		1	EA		
53	820250	REMOVE ROADSIDE SIGN		9	EA		
54	820610	RELOCATE ROADSIDE SIGN		1	EA		
55	820750	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)		7	SQFT		
56	820840	ROADSIDE SIGN - ONE POST		1	EA		
57	833088	TUBULAR HANDRAILING	F	479	LF		
58	839521	CABLE RAILING	F	11	LF		
59	839543	TRANSITION RAILING (TYPE WB-31)		2	EA		
60	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM		2	EA		
61	839607	CRASH CUSHION (QUADGUARD)		1	EA		
62	839713	CONCRETE BARRIER (TYPE 85)	F	499	LF		
63	840505	6" THERMOPLASTIC TRAFFIC STRIPE		540	LF		

Name of Bidder_____

64	840515	THERMOPLASTIC PAVEMENT MARKING		53	SQFT		
65	999990	MOBILIZATION		1	LS	LUMP SUM	
BASE BID SUBTOTAL							

**TOTAL
BASE BID**

Name of Bidder_____

Signature of Bidder_____

Printed Name and Title_____

Date_____