



List of Bid Items

Note: *This list is not updated when addenda are issued. For informational purposes only.*

Contract Number **05-1Q03U4**

Date Adv.: 09/03/2024

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0001	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
0002	080060	LEVEL 2 CRITICAL PATH METHOD SCHEDULE	LS	LUMP SUM
0003	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	180
0004	090200	DISPUTE RESOLUTION ADVISOR ON-SITE MEETING	EA	5
0005	090207	HOURLY OFF-SITE DISPUTE-RESOLUTION-ADVISOR-RELATED TASKS	HR	10
0006	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
0007	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
0008	120110	FLASHING ARROW SIGN	EA	1
0009	120149	TEMPORARY PAVEMENT MARKING (PAINT)	SQFT	380
0010	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	62,900
0011	120165	CHANNELIZER (SURFACE MOUNTED)	EA	69
0012	120300	TEMPORARY PAVEMENT MARKER	EA	1,270
0013	120320	TEMPORARY BARRIER SYSTEM	LF	10,200
0014	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM
0015	129108	TEMPORARY CRASH CUSHION TL-3	EA	10

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0016	129152	TEMPORARY RADAR SPEED FEEDBACK SIGN SYSTEM	EA	2
0017	129161	AUTOMATED FLAGGER ASSISTANCE DEVICE DAY	EA	8
0018	130100	JOB SITE MANAGEMENT	LS	LUMP SUM
0019	130301	STORMWATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
0020	130320	STORM WATER SAMPLING AND ANALYSIS DAY	EA	5
0021	130330	STORM WATER ANNUAL REPORT	EA	2
0022	130505	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	EA	3
0023	130530	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQYD	40,000
0024	130610	TEMPORARY CHECK DAM	LF	200
0025	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	4
0026	130640	TEMPORARY FIBER ROLL	LF	2,500
0027	130650	TEMPORARY GRAVEL BAG BERM	LF	250
0028	130660	TEMPORARY LARGE SEDIMENT BARRIER	LF	500
0029	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	3
0030	130730	STREET SWEEPING	LS	LUMP SUM
0031	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM
0032	141120	TREATED WOOD WASTE	LB	1,330
0033	146007	INVASIVE SPECIES CONTROL	LS	LUMP SUM
0034	170103	CLEARING AND GRUBBING (LS)	LS	LUMP SUM
0035	190101	ROADWAY EXCAVATION	CY	13,200
0036	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	8,000

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0037	210430	HYDROSEED	SQFT	118,000
0038	210610	COMPOST (CY)	CY	1,160
0039	210630	INCORPORATE MATERIALS	SQFT	71,000
0040	260203	CLASS 2 AGGREGATE BASE (CY)	CY	6,390
0041	390132	HOT MIX ASPHALT (TYPE A)	TON	7,280
0042	390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	2,140
0043	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	500
0044	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	15
0045	397005	TACK COAT	TON	6
0046	398200	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	3,790
0047	510090	(F) - STRUCTURAL CONCRETE, BOX CULVERT	CY	49
0048	510092	(F) - STRUCTURAL CONCRETE, HEADWALL	CY	13
0049	510094	(F) - STRUCTURAL CONCRETE, DRAINAGE INLET	CY	3.5
0050	520101	(F) - BAR REINFORCING STEEL	LB	9,950
0051	610112	24" ALTERNATIVE PIPE CULVERT	LF	74
0052	710132	REMOVE CULVERT (LF)	LF	75
0053	710150	REMOVE INLET	EA	1
0054	710152	REMOVE HEADWALL	EA	2
0055	710167	REMOVE FLARED END SECTION (EA)	EA	2
0056	750001	(F) - MISCELLANEOUS IRON AND STEEL	LB	188
0057	013418	FENCE (TYPE WM, MODIFIED, 4')	LF	800
0058	810120	REMOVE PAVEMENT MARKER	EA	430

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0059	810170	DELINEATOR (CLASS 1)	EA	10
0060	810230	PAVEMENT MARKER (RETROREFLECTIVE)	EA	550
0061	820113	TREATMENT BEST MANAGEMENT PRACTICE MARKER	EA	10
0062	820130	OBJECT MARKER	EA	11
0063	820250	REMOVE ROADSIDE SIGN	EA	11
0064	820750	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	27
0065	820790	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	SQFT	49
0066	820840	ROADSIDE SIGN - ONE POST	EA	3
0067	820850	ROADSIDE SIGN - TWO POST	EA	2
0068	839521	(F) - CABLE RAILING	LF	73
0069	839752	REMOVE GUARDRAIL	LF	360
0070	840516	THERMOPLASTIC PAVEMENT MARKING (ENHANCED WET NIGHT VISIBILITY)	SQFT	88
0071	840623	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (BROKEN 36-12)	LF	1,570
0072	846007	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	19,800
0073	846030	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	14,900
0074	846035	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	130
0075	846051	12" RUMBLE STRIP (ASPHALT CONCRETE PAVEMENT)	STA	130
0076	847214	6" TRAFFIC STRIPE TAPE (WARRANTY) (BROKEN 36-12)	LF	5,400

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0077	872135	MODIFYING TRAFFIC MONITORING STATIONS	LS	LUMP SUM
0078	999990	MOBILIZATION	LS	LUMP SUM

[Back to Top](#)

[Accessibility](#)



[Privacy Policy](#)

[Conditions of Use](#)



Copyright © 2024 State of California