

BID ITEM LIST

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0001	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
0002	080060	LEVEL 2 CRITICAL PATH METHOD SCHEDULE	LS	LUMP SUM
0003	090105	TIME-RELATED OVERHEAD (LS)	LS	LUMP SUM
0004	090200	DISPUTE RESOLUTION ADVISOR ON-SITE MEETING	EA	12
0005	090207	HOURLY OFF-SITE DISPUTE-RESOLUTION-ADVISOR-RELATED TASKS	HR	20
0006	100100	DEVELOP WATER SUPPLY	LS	LUMP SUM
0007	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
0008	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
0009	120103	STATIONARY IMPACT ATTENUATOR VEHICLE	DAY	120
0010	010413	PORTABLE RADAR SPEED FEEDBACK SIGN SYSTEMS (LS)	LS	LUMP SUM
0011	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM
0012	129100	TEMPORARY CRASH CUSHION MODULE	EA	50
0013	129161	AUTOMATED FLAGGER ASSISTANCE DEVICE DAY	EA	10
0014	130100	JOB SITE MANAGEMENT	LS	LUMP SUM
0015	130201	WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM
0016	130510	TEMPORARY MULCH	SQYD	10,500
0017	130570	TEMPORARY COVER	SQYD	10,500
0018	130610	TEMPORARY CHECK DAM	LF	860
0019	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	64
0020	130640	TEMPORARY FIBER ROLL	LF	510

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0021	130650	TEMPORARY GRAVEL BAG BERM	LF	80
0022	130680	TEMPORARY SILT FENCE	LF	5,950
0023	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	38
0024	130720	TEMPORARY CONSTRUCTION ROADWAY	SQYD	5,920
0025	130730	STREET SWEEPING	LS	LUMP SUM
0026	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM
0027	131103	WATER QUALITY SAMPLING AND ANALYSIS DAY	EA	66
0028	131104	WATER QUALITY MONITORING REPORT	EA	17
0029	131105	WATER QUALITY ANNUAL REPORT	EA	3
0030	131201	TEMPORARY CREEK DIVERSION SYSTEMS	LS	LUMP SUM
0031	146002	CONTRACTOR-SUPPLIED BIOLOGIST (LS)	LS	LUMP SUM
0032	146007	INVASIVE SPECIES CONTROL	LS	LUMP SUM
0033	013843	CONTRACTOR SUPPLIED ARBORIST	LS	LUMP SUM
0034	160110	TEMPORARY HIGH-VISIBILITY FENCE	LF	1,780
0035	160220	TEMPORARY CONSTRUCTION MAT (LS)	LS	LUMP SUM
0036	170103	CLEARING AND GRUBBING (LS)	LS	LUMP SUM
0037	194001	DITCH EXCAVATION	CY	90
0038	205035	WOOD MULCH	CY	1,930
0039	210010	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	3
0040	037634	HYDRAULIC BIOTIC GROWTH MEDIUM	SQFT	84,500

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0041	210255	FIBER REINFORCED MATRIX (SQFT)	SQFT	84,500
0042	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	130,000
0043	210350	FIBER ROLLS	LF	7,350
0044	210610	COMPOST (CY)	CY	560
0045	210630	INCORPORATE MATERIALS	SQFT	73,400
0046	260203	CLASS 2 AGGREGATE BASE (CY)	CY	10
0047	390132	HOT MIX ASPHALT (TYPE A)	TON	2.7
0048	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	78
0049	394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	41
0050	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	13
0051	398100	REMOVE ASPHALT CONCRETE DIKE	LF	64
0052	510050	(F) - STRUCTURAL CONCRETE	CY	6
0053	510092	(F) - STRUCTURAL CONCRETE, HEADWALL	CY	42
0054	510094	(F) - STRUCTURAL CONCRETE, DRAINAGE INLET	CY	51
0055	510501	(F) - MINOR CONCRETE	CY	1
0056	600011	RAPID SETTING CONCRETE (PATCH)	CF	110
0057	610101	8" ALTERNATIVE PIPE CULVERT	LF	3
0058	610112	24" ALTERNATIVE PIPE CULVERT	LF	520
0059	610121	36" ALTERNATIVE PIPE CULVERT	LF	73
0060	610300	(F) - CONCRETE BACKFILL (PIPE TRENCH)	CY	87

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0061	015420	CONCRETE COLLAR	EA	1
0062	665008	10" CORRUGATED STEEL PIPE (.064" THICK)	LF	10
0063	665012	12" CORRUGATED STEEL PIPE (.079" THICK)	LF	24
0064	665018	18" CORRUGATED STEEL PIPE (.109" THICK)	LF	20
0065	665024	24" CORRUGATED STEEL PIPE (.109" THICK)	LF	1,840
0066	665037	36" CORRUGATED STEEL PIPE (.109" THICK)	LF	520
0067	665043	42" CORRUGATED STEEL PIPE (.138" THICK)	LF	710
0068	665053	54" CORRUGATED STEEL PIPE (.168" THICK)	LF	190
0069	665055	60" CORRUGATED STEEL PIPE (.109" THICK)	LF	95
0070	680406	8" PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK)	LF	92
0071	680412	12" PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK)	LF	10
0072	690106	8" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	5
0073	690124	24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	1,290
0074	690132	30" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	5
0075	690137	36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	370
0076	690142	42" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	180
0077	017097	60" CORRUGATED STEEL PIPE DOWNDRAIN (0.109" THICK)	LF	150
0078	013917	CABLE ANCHORAGE SYSTEM (MOD)	EA	22
0079	700615	CORRUGATED STEEL PIPE INLET	LF	71
0080	014911	36" WELDED STEEL PIPE TRENCHLESS INSTALLATION METHOD	LF	440

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0081	014912	42" WELDED STEEL PIPE TRENCHLESS INSTALLATION METHOD	LF	150
0082	017096	60" WELDED STEEL PIPE TRENCHLESS INSTALLATION METHOD	LF	680
0083	705015	24" STEEL FLARED END SECTION	EA	15
0084	705023	36" STEEL FLARED END SECTION	EA	1
0085	705027	42" STEEL FLARED END SECTION	EA	2
0086	705035	54" STEEL FLARED END SECTION	EA	1
0087	038552	60" STEEL FLARED END SECTION	EA	5
0088	710102	ABANDON CULVERT (LF)	LF	2,400
0089	710132	REMOVE CULVERT (LF)	LF	4,500
0090	710138	REMOVE DOWNDRAIN (EA)	EA	19
0091	710150	REMOVE INLET	EA	26
0092	710152	REMOVE HEADWALL	EA	4
0093	710160	REMOVE JUNCTION BOX	EA	3
0094	710165	REMOVE CONCRETE FLARED END SECTION (EA)	EA	1
0095	710167	REMOVE FLARED END SECTION (EA)	EA	15
0096	710366	CONCRETE INVERT PAVING	CY	35
0097	710368	CULVERT SLURRY-CEMENT BACKFILL	CY	610
0098	721431	CONCRETE (CONCRETE APRON)	CY	22
0099	013729	GRAVEL FILTER	CY	190
0100	723015	ROCK SLOPE PROTECTION (2T, CLASS IX, METHOD A)	CY	62

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0101	723020	ROCK SLOPE PROTECTION (1T, CLASS VIII, METHOD A)	CY	330
0102	723030	ROCK SLOPE PROTECTION (1/2 T, CLASS VII, METHOD A) (CY)	CY	68
0103	723050	ROCK SLOPE PROTECTION (1/4 T, CLASS V, METHOD B) (CY)	CY	180
0104	723060	ROCK SLOPE PROTECTION (300 LB, CLASS IV, METHOD B) (CY)	CY	24
0105	723070	ROCK SLOPE PROTECTION (150 LB, CLASS III, METHOD B) (CY)	CY	45
0106	723080	ROCK SLOPE PROTECTION (60 LB, CLASS II, METHOD B) (CY)	CY	240
0107	723095	ROCK SLOPE PROTECTION (20 LB, CLASS I, METHOD B) (CY)	CY	11
0108	750001	(F) - MISCELLANEOUS IRON AND STEEL	LB	7,660
0109	820112	MARKER (CULVERT)	EA	66
0110	820113	TREATMENT BEST MANAGEMENT PRACTICE MARKER	EA	8
0111	820220	REMOVE MARKER	EA	66
0112	839521	(F) - CABLE RAILING	LF	88
0113	870009	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM
0114	999990	MOBILIZATION	LS	LUMP SUM