



851 Martin Ave.
Santa Clara, CA 95050
408.727.5700
CA Contractors License CA299880
ID Contractors License RCE-61910
UT Contractors License 12806060-5501

Invitation to Bid: DBE Subcontractors & Suppliers

Project Name: Caltrans 05-1H6504
Owner: State of California Department of Transportation
Bid Due Date: Wednesday, December 18, 2024, at Noon
Overall DBE Goal 22% for:

Locating	Lead Compliance Plan	Place AC Dike
CPM Scheduling	Construction Area Signs	Data Coring
Barricades	Traffic Control Systems and Related Items	Drilling
Temporary Barrier	Temporary Paint Marking and Stripe	Fencing
PCMS	Automated Flagger Devices	Bar Reinforcing Steel
Water System	Structural Concrete & Related Items	Precast Concrete
Delineators	Traffic Stripe and Markings	Steel Beams
Hydroseed	Channelizers and Markers	Coating & Painting
Arborist	Erosion Control (Temp and Perm)	Anodes
Clear and Grub	WPCP and Related Items	Underground
Demolition	Storm Water Sampling and Analysis	Storm Drains
Noise Monitoring	Temporary Creek Diversion	Water Systems
Cold Plane	Treated Wood Waste	Concrete Grinding
Site Furnishings	Salvage Railroad Crossing Arms	Concrete Deck Treatment
Earthwork & Grading	Soldier Pile Wall	Bridge Removal
Tack Coat	Landscape & Irrigation	Noise Monitoring
Asphalt Paving	Misc. Iron & Steel	Rock Slope Protection
Stamped Concrete	Minor Concrete & Related Items	Concrete Staining
Bus Shelter	Survey / Staking & Related Tasks	Roadside Signs
Concrete Barrier	Guardrail	Lighting
Signals	Electric	Street Sweeping
Trucking	Aggregate Base Material	Ready Mix Concrete
HMA Material	RHMA Material	

Project Description: HMA (Type A), RHMA-G, Drainage, Landscape, Electrical and Curb Ramps.

**Contact/Bid Submission/
Scope Questions:** Dan McHale or John Gasiorowski, Estimators
Estimating@jialbanese.com
Phone: 408-727-5700; Fax: 1-408-727-0366

Payment and Performance Bond may be required. Please provide bond premium with bid. Contractor must have valid contractor's license for work bid, and current DIR #.

Contact for: Bond and Insurance inquiry referral, line of credit referral, equipment rental. Section 3 Small Business Concern certification assistance, or other assistance, contact: Nicole Alise, Ph. 408-727-5700, nalise@jialbanese.com

Bid Documents: <https://jialbanese.egnyte.com/fl/7RfGDQpvqi>

Company/Contact Name: _____ DIR #: _____ Phone: _____

Email: _____ DBE #: _____ Union(s): _____

Jos. J. Albanese, Inc. is an Equal Opportunity Employer

Joseph J Albanese, Inc. is signatory to the carpenter, cement mason, laborer, ironworker, block mason and operator unions.

www.jialbanese.com

BID ITEM LIST

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0001	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM
0002	080060	LEVEL 2 CRITICAL PATH METHOD SCHEDULE	LS	LUMP SUM
0003	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	350
0004	090205	DISPUTE RESOLUTION BOARD ON-SITE MEETING	EA	7
0005	090210	HOURLY OFF-SITE DISPUTE-RESOLUTION-BOARD-RELATED TASKS	HR	40
0006	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
0007	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
0008	120103	STATIONARY IMPACT ATTENUATOR VEHICLE	DAY	100
0009	120120	TYPE III BARRICADE	EA	120
0010	120151	TEMPORARY TRAFFIC STRIPE (TAPE)	LF	56,200
0011	120152	TEMPORARY PAVEMENT MARKING (TAPE)	SQFT	3,250
0012	120165	CHANNELIZER (SURFACE MOUNTED)	EA	12
0013	120195	TRAFFIC DRUM	EA	1,730
0014	120207	PORTABLE RADAR SPEED FEEDBACK SIGN SYSTEM	DAY	640
0015	120300	TEMPORARY PAVEMENT MARKER	EA	1,690
0016	124000	TEMPORARY PEDESTRIAN ACCESS ROUTE	LS	LUMP SUM
0017	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM
0018	129152	TEMPORARY RADAR SPEED FEEDBACK SIGN SYSTEM	EA	2
0019	129161	AUTOMATED FLAGGER ASSISTANCE DEVICE DAY	EA	20
0020	130100	JOB SITE MANAGEMENT	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0021	130301	STORMWATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
0022	130320	STORM WATER SAMPLING AND ANALYSIS DAY	EA	18
0023	130330	STORM WATER ANNUAL REPORT	EA	2
0024	130505	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	EA	12
0025	130530	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQYD	23,000
0026	130610	TEMPORARY CHECK DAM	LF	100
0027	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	6
0028	130640	TEMPORARY FIBER ROLL	LF	1,150
0029	130650	TEMPORARY GRAVEL BAG BERM	LF	440
0030	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	4
0031	130730	STREET SWEEPING	LS	LUMP SUM
0032	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM
0033	141120	TREATED WOOD WASTE	LB	48,400
0034	148005	NOISE MONITORING	LS	LUMP SUM
0035	013733	SALVAGE BENCH	EA	11
0036	153121	REMOVE CONCRETE (CY)	CY	5
0037	153123	REMOVE CONCRETE (SQYD)	SQYD	11,100
0038	017176	SALVAGE RAILROAD CROSSING ARMS	LS	LUMP SUM
0039	160110	TEMPORARY HIGH-VISIBILITY FENCE	LF	1,430
0040	170103	CLEARING AND GRUBBING (LS)	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0041	190101	ROADWAY EXCAVATION	CY	5,830
0042	190185	SHOULDER BACKING	TON	83
0043	192037	(F) - STRUCTURE EXCAVATION (RETAINING WALL)	CY	221
0044	193013	(F) - STRUCTURE BACKFILL (RETAINING WALL)	CY	127
0045	198207	SUBGRADE ENHANCEMENT GEOTEXTILE, CLASS A2	SQYD	1,210
0046	200113	ROCK MULCH	SQFT	9
0047	200114	ROCK BLANKET	SQFT	2,300
0048	202006	SOIL AMENDMENT	CY	8
0049	202038	PACKET FERTILIZER	EA	550
0050	202039	SLOW-RELEASE FERTILIZER	LB	33
0051	203100	SOIL TESTING	EA	3
0052	204011	PLANT (GROUP K)	EA	65
0053	204020	PLANT (GROUP P)	EA	1,280
0054	204035	PLANT (GROUP A)	EA	310
0055	014899	TREE PROTECTION	EA	1
0056	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
0057	205035	WOOD MULCH	CY	24
0058	205062	ROOT BARRIER	LF	840
0059	038007	TREE GRATE	EA	54
0060	016190	PEDESTRIAN GRATE	EA	30

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0061	038008	TREE GUARD	EA	54
0062	015073	BIKE RACK	EA	10
0063	206560	CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM
0064	206561	3/4" REMOTE CONTROL VALVE	EA	6
0065	206921	SOLAR POWERED IRRIGATION CONTROLLER	EA	2
0066	016067	SOLAR POWERED BOLLARD (LIGHTED)	EA	10
0067	208422	3/4" BACKFLOW PREVENTER ASSEMBLY	EA	2
0068	016068	TREE WATER BAGS	EA	19
0069	208445	TREE WELL SPRINKLER ASSEMBLY	EA	38
0070	208449	POP-UP SPRINKLER ASSEMBLY	EA	82
0071	208594	(F) - 3/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	6,190
0072	208596	(F) - 1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	310
0073	016069	BENCH (TYPE A)	EA	11
0074	016070	BENCH (TYPE B)	EA	4
0075	208683	BALL VALVE	EA	6
0076	208690	PVC PIPE CONDUIT (SLEEVE)	LF	3,350
0077	208738	8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	120
0078	016191	IMPORTED SOIL MEDIA	CY	61
0079	210430	HYDROSEED	SQFT	18,000
0080	210610	COMPOST (CY)	CY	55

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0081	210630	INCORPORATE MATERIALS	SQFT	18,000
0082	211111	PERMANENT EROSION CONTROL ESTABLISHMENT WORK	LS	LUMP SUM
0083	260203	CLASS 2 AGGREGATE BASE (CY)	CY	3,830
0084	290301	CEMENT TREATED PERMEABLE BASE	CY	47
0085	390025	SEGMENT CORRECTION	EA	24
0086	390095	REPLACE ASPHALT CONCRETE SURFACING	CY	440
0087	390132	HOT MIX ASPHALT (TYPE A)	TON	9,140
0088	390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	6,870
0089	394060	DATA CORE	LS	LUMP SUM
0090	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	1,760
0091	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	19
0092	397005	TACK COAT	TON	46
0093	398001	REMOVE ASPHALT CONCRETE PAVEMENT (SQFT)	SQFT	2,110
0094	398100	REMOVE ASPHALT CONCRETE DIKE	LF	1,170
0095	398200	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	51,500
0096	048593	RETAINING WALL STEM (TYPE 6A MODIFIED)	SQFT	1,049
0097	510060	(F) - STRUCTURAL CONCRETE, RETAINING WALL	CY	25
0098	510094	(F) - STRUCTURAL CONCRETE, DRAINAGE INLET	CY	8
0099	038029	STRUCTURAL CONCRETE (BUS PAD)	CY	51
0100	511111	DRILL AND BOND DOWEL (CHEMICAL ADHESIVE) (LF)	LF	44

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0101	520103	(F) - BAR REINFORCING STEEL (RETAINING WALL)	LB	2,921
0102	037494	WELDED WIRE REINFORCEMENT 4" X 4" W1.4/W1.4	SQYD	50
0103	568062	PEDESTRIAN BARRICADE	EA	1,470
0104	016071	PEDESTRIAN BARRICADE RAILING	LF	250
0105	016072	PEDESTRIAN BULBOUT RAILING	LF	100
0106	600001	PUBLIC SAFETY PLAN	LS	LUMP SUM
0107	600011	RAPID SETTING CONCRETE (PATCH)	CF	144
0108	600013	REPAIR SPALLED SURFACE AREA	SQFT	60
0109	600017	REMOVE RETAINING WALL (LF)	LF	209
0110	600033	REMOVE UNSOUND CONCRETE	CF	144
0111	600037	PREPARE CONCRETE BRIDGE DECK SURFACE	SQFT	13,693
0112	600045	(F) - TREAT BRIDGE DECK	SQFT	13,693
0113	600047	FURNISH BRIDGE DECK TREATMENT MATERIAL	GAL	137
0114	600065	CORE CONCRETE (3")	LF	1
0115	600066	CORE CONCRETE (4")	LF	6
0116	600114	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM
0117	650014	18" REINFORCED CONCRETE PIPE	LF	24
0118	650018	24" REINFORCED CONCRETE PIPE	LF	25
0119	680283	3" PLASTIC PIPE UNDERDRAIN	LF	230
0120	681132	GEOCOMPOSITE DRAIN	SQFT	271

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0121	690117	18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	9
0122	692007	18" ENTRANCE TAPER	EA	1
0123	692207	18" DOWNDRAIN SLIP JOINT	EA	1
0124	692307	18" ANCHOR ASSEMBLY	EA	3
0125	700617	DRAINAGE INLET MARKER	EA	6
0126	702600	DOWNDRAIN ENERGY DISSIPATOR	EA	1
0127	710132	REMOVE CULVERT (LF)	LF	94
0128	710138	REMOVE DOWNDRAIN (EA)	EA	1
0129	710150	REMOVE INLET	EA	1
0130	010313	ADJUST MANHOLE TO GRADE	EA	12
0131	710196	ADJUST INLET	EA	3
0132	710368	CULVERT SLURRY-CEMENT BACKFILL	CY	10
0133	723080	ROCK SLOPE PROTECTION (60 LB, CLASS II, METHOD B) (CY)	CY	3.2
0134	729011	ROCK SLOPE PROTECTION FABRIC (CLASS 8)	SQYD	12
0135	730020	MINOR CONCRETE (CURB) (CY)	CY	570
0136	048594	MINOR CONCRETE (CONCRETE SLAB)	CY	5
0137	730045	MINOR CONCRETE (GUTTER) (CY)	CY	180
0138	730070	DETECTABLE WARNING SURFACE	SQFT	2,130
0139	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	CY	12
0140	731516	MINOR CONCRETE (DRIVEWAY)	CY	320

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0141	731519	MINOR CONCRETE (STAMPED CONCRETE)	SQFT	6,060
0142	731521	MINOR CONCRETE (SIDEWALK)	CY	530
0143	016073	MINOR CONCRETE DRIVEWAY (HIGH EARLY STRENGTH)	CY	120
0144	731623	MINOR CONCRETE (CURB RAMP)	CY	260
0145	733000	PRE/POST CONSTRUCTION SURVEYS	EA	5
0146	016074	BUS STOP SHELTER (END SCREEN)	EA	4
0147	016075	BUS STOP SHELTER ASSEMBLY	EA	8
0148	750001	(F) - MISCELLANEOUS IRON AND STEEL	LB	717
0149	014901	WATER SERVICE	LS	LUMP SUM
0150	037108	RELOCATE FIRE HYDRANT	EA	13
0151	010525	ADJUST FIRE HYDRANT TO GRADE	EA	1
0152	048595	DECORATIVE COLUMN	EA	3
0153	780230	SURVEY MONUMENT (TYPE D)	EA	7
0154	015370	ADJUST UTILITY BOX AND COVER TO GRADE	EA	140
0155	780433	PAINT CURB (2-COAT)	SQFT	5,090
0156	780440	PREPARE AND STAIN CONCRETE	SQFT	656
0157	800360	CHAIN LINK FENCE (TYPE CL-6)	LF	86
0158	810120	REMOVE PAVEMENT MARKER	EA	1,830
0159	810230	PAVEMENT MARKER (RETROREFLECTIVE)	EA	910
0160	820250	REMOVE ROADSIDE SIGN	EA	150

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0161	820750	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	1,900
0162	820760	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	59
0163	820780	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	SQFT	38
0164	820790	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	SQFT	240
0165	820840	ROADSIDE SIGN - ONE POST	EA	170
0166	820850	ROADSIDE SIGN - TWO POST	EA	4
0167	820860	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	53
0168	820880	INSTALL SIGN (MAST-ARM HANGER METHOD)	EA	2
0169	820900	INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	EA	47
0170	048332	CONCRETE BARRIER (PORTION)	LF	372
0171	839752	REMOVE GUARDRAIL	LF	430
0172	840617	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (BROKEN 6-1)	LF	290
0173	840623	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (BROKEN 36-12)	LF	4,720
0174	846007	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	32,600
0175	846008	6" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY) (BROKEN 8-4)	LF	3,120
0176	846009	8" THERMOPLASTIC TRAFFIC STRIPE (ENHANCED WET NIGHT VISIBILITY)	LF	1,320
0177	846012	THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING (ENHANCED WET NIGHT VISIBILITY)	SQFT	7,750
0178	846030	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	31,400
0179	846035	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	3,500
0180	847148	METHYL METHACRYLATE PAINT TRAFFIC STRIPE CROSSWALK AND PAVEMENT MARKING	SQFT	5,600

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
0181	847213	6" TRAFFIC STRIPE TAPE (WARRANTY) (BROKEN 17-7)	LF	2,410
0182	870009	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM
0183	013849	MONUMENT LIGHTING SYSTEMS	LS	LUMP SUM
0184	870600	TRAFFIC MONITORING STATION SYSTEM	LS	LUMP SUM
0185	037568	RECTANGULAR RAPID FLASHING BEACON SYSTEMS	LS	LUMP SUM
0186	871300	CAMERA SYSTEMS	LS	LUMP SUM
0187	872133	MODIFYING SIGNAL AND LIGHTING SYSTEMS	LS	LUMP SUM
0188	995100	WATER METER CHARGES	LS	LUMP SUM
0189	995200	IRRIGATION WATER SERVICE CHARGES	LS	LUMP SUM
0190	999990	MOBILIZATION	LS	LUMP SUM